MAP FOR EUREKA COUNT

WELL STREE RIDGETOP RD. CANYON SUB'N VICINITY MAP (NOT TO SCALE) SITE EUREKA STATE OF

OWNER'S CERTIFICATES

BEING FIRST DULY SWORN, THE UNDERSIGNED, EUREKA COUNTY, A POLITICAL SUBDIVISION OF THE STATE OF NEVADA, AFFIRMS AND SAYS THAT THEY ARE THE OWNER OF THE LAND TO BE DIVIDED BY THIS MAP, AND WE CONSENT TO THIS LAND DIVISION. WE HEREBY GRANT THE EASEMENTS SHOWN AND NOTED HEREON.

COUNTY OF EUREKA TO BEFORE ME A NOTARY PUBLIC DAY OF OCIONAL, 2017, INSTRUMENT, IN WITNESS WHEREOF, I HEREUNTO SET MY SEAL THE DATE AND YEAR FIRST WRITTEN ABOVE. N AND FOR SAID STATE AND

OLITICAL SUBDIVISION OF THE STATE OF NEVADA

REFERENCES

EUREKA COUNTY TREASURER



9) RECORD OF SURVEY SUPPORTING A LOT LINE ADJUSTMENT FOR WILLIAM E. & ROBIN R. HICKS AND EUREKA COUNTY, RECORDED FEBRUARY 24, 1999 AS FILE NUMBER 171933, OFFICIAL RECORDS OF EUREKA COUNTY, NEVADA.

11) AMENDED PARCEL MAP FOR WILLIAM E. & ROBIN R. HICKS, RECORDED JUNE 1999 AS FILE NUMBER 172264, OFFICIAL RECORDS OF EUREKA COUNTY, NEVADA. 10) GRANT, BARGAIN, AND SALE DEED BETWEEN WILLIAM E. & ROBIN R. HICKS AND EUREKA COUNTY, RECORDED MARCH 3, 1999 AS DOCUMENT NUMBER 171966, OFFICIAL RECORDS OF EUREKA COUNTY, NEVADA.

14) PRELIMINARY TITLE REPORT PREPARED BY STEWART TITLE, DATED MARCH 5, 2013, ORDER No. 01415-2997. 12) PARCEL MAP FOR PHIL BROWN WELDING & REPAIR, RECORDED JULY 8, 2002 AS FILE NUMBER 178257, OFFICIAL RECORDS OF EUREKA COUNTY, NEVADA. 3) PARCEL MAP FOR WILLIAM E. & ROBIN R. HICKS, RECORDED OCTOBER 29, 2008 AS FILE NUMBER 212688, OFFICIAL RECORDS OF EUREKA COUNTY, NEVADA.

NOTES:

1) PLAT AND NOTES OF THE EUREKA TOWNSITE, EUREKA, NEVADA. APPROVED BY THE SUPERVISOR OF SURVEYS ON SEPTEMBER 14, 1937 AND ACCEPTED BY THE ASSISTANT COMMISSIONER OF THE GENERAL LAND OFFICE, DEPARTMENT OF INTERIOR, UNITED STATES ON NOVEMBER 19, 1937.

5) PARCEL MAP FOR JACK SCOTT BURNETT, RECORDED JUNE 20, 1990 AS FILE NUMBER 132576, OFFICIAL RECORDS OF EUREKA COUNTY, NEVADA. 6) RECORD OF SURVEY OF APN 1-171-01 FOR EUREKA COUNTY, RECORDED OCTOBER 24, 1996 AS FILE NUMBER 164852, OFFICIAL RECORDS OF EUREKA COUNTY, NEVADA. 4) PLAT OF THE TOWNSITE OF EUREKA, NEVADA, RECORDED JUNE 20, 1989 AS FILE NUMBER 127447, OFFICIAL RECORDS OF EUREKA COUNTY, NEVADA. 3) PARCEL MAP FOR TODD & TINA HUBBARD, RECORDED SEPTEMBER 1, 1987 AS FILE NUMBER 111007, OFFICIAL RECORDS OF EUREKA COUNTY, NEVADA. 2) RECORD OF SURVEY OF PORTIONS OF BLOCKS 103 & 104, RECORDED JULY 7, 1987 AS FILE NUMBER 109280, OFFICIAL RECORDS OF EUREKA COUNTY, NEVADA.

8) RECORD OF SURVEY OF RIGHT-OF-WAY DEDICATION FOR EUREKA COUNTY PUBLIC WORKS, RECORDED FEBRUARY 24, 1999 AS FILE NUMBER 171932, OFFICIAL RECORDS OF EUREKA COUNTY, NEVADA. 7) PARCEL MAP FOR WILLIAM E. & ROBIN R. HICKS, RECORDED AUGUST 6, 1998 AS FILE NUMBER 170339, OFFICIAL RECORDS OF EUREKA COUNTY, NEVADA.

MARTIN APN 001-186-10 POR. BLK 123

WELL STREET

ROWLEY APN 001-187-01 LOTS 1-4 BLK 120

B SOUR STARK

FOUND BENT

LOT 4 BLK 120

1 Raisi

√10' PUĖ, SSE, WLE, SDE, & DE

BASQUE STREET

FOUND 5/8" REBAR & CAP PLS 6304

FOUND 5/8" REBAR & CAP PLS 3144

PUBLIC UTILITY EASEMENTS, SANITARY SEWER EASEMENT, WATERLINE EASEMENT, STORM IN AND DRAINAGE EASEMENTS ARE HEREBY GRANTED 10 FEET IN WIDTH ADJACENT TO PARCEL LINES.

. PUBLIC UTILITY EASEMENTS ARE HEREBY GRANTED WITHIN EACH LOT FOR THE XCLUSIVE PURPOSE OF INSTALLING AND MAINTAINING UTILITY SERVICE FACILITIES TO EACH OT AND THE RIGHT TO EXIT EACH LOT TO SERVE ADJOINING LOTS AT LOCATIONS OF AUTUALLY AGREED UPON BY THE OWNER OF RECORD AT THE TIME OF INSTALLATION AND HE UTILITY COMPANY.

5. BASIS OF BEARINGS: NORTH AMERICAN DATUM OF 1983 AS BASED ON FEDERAL BASE NETWORK/COOPERATIVE BASE NETWORK OBSERVATIONS IN 1994 (AKA NAD83/94), NEVADA STATE PLANE EAST ZONE. GROUND COORDINATES HEREON REFLECT GRID COORDINATES DIVIDED BY THE NEVADA DEPARTMENT OF TRANSPORTATION (NDOT) COMBINED GRID TO GROUND FACTOR OF 1.000386.

BROWN APN 001-186-09 POR. BLK 123

FOUND 1/2" REBAR N 2.7', E 0.55', NOT ACCEPTED

SDE, & DE

FOUND 5/8" REBAR & CAP PLS 3144

WLE, SDE,

\$ 05.07'20" E 139.04 {\$05.26'38" E 138.83 R8&R9}

PARCEL B [30,427± SF]

ACCESS, PUE, SSE,

_10' PUE, SSE, WLE, SDE, & DE

10' PUE, SSE, LE, SDE, & DE

FOUND 5/8" REB/ & CAP PLS 7998

BURNETT APN 001-194-04 POR. MILL SITE SURVEY 94

4. OWNER OF APN 001-187-03: EUREKA COUNTY, A POLITICAL SUBDIVISION STATE OF NEVADA, WHOSE ADDRESS IS P.O. BOX 100, EUREKA, NV 89316.). THE NATURAL DRAINAGE WILL NOT BE IMPEDED DURING CONSTRUCTION OR MPROVEMENT OF THE PARCELS SHOWN HEREON.

TOTAL AREA OF PARCELS = 59,722± SQUARE TOTAL NUMBER OF RESULTANT PARCELS = 2.

SURVEYOR'S CERTIFICATE

I, RYAN G. COOK, A CERTIFY THAT:

PROFESSIONAL LAND SURVEYOR LICENSED IN THE STATE OF NEVADA

1. THIS PLAT REPRESENTS THE RESULTS OF A SURVEY CONDUCTED UNDER MY DIRECT SUPERVISION AT THE INSTANCE OF EUREKA COUNTY, A POLITICAL SUBDIVISION OF THE STATE OF NEVADA.

THIS IS TO CERTIFY THAT ASSESSOR'S PARCEL NO. 001-187-03 have no delinquencies and that taxes are paid through -EXEMP

COUNTY TREASURER'S CERTIFICATE

3. THIS PLAT COMPLIES WITH THE APPLICABLE STATE STATUTES AND ANY LOCAL ORDINANCES IN EFFECT ON THE DATE THAT THE GOVERNING BODY GAVE ITS FINAI APPROVAL. 2. THE LANDS SURVEYED LIE WITHIN THE NORTHEAST QUARTER OF SECTION 23 AND THE NORTHWEST QUARTER OF SECTION 24, TOWNSHIP 19 NORTH, RANGE 53 EAST, M.D.M. AND THE SURVEY WAS COMPLETED ON OCTOBER 8, 2013.

4. THE MONUMENTS DEPICTED ON THE PLAT ARE OF THE CHARACTER SHOWN, OCCUPY THE POSITIONS INDICATED AND ARE OF SUFFICIENT NUMBER AND DURABILITY.




WATER RIGHTS DEDICATION

APPLICANT: EUREKA COUNTY, A THIS IS TO CERTIFY THAT ON THE HAS COMPLIED WITH THE REQUIRENEN WATER RIGHTS DEDICATION. DAY OF _____, 20__ THE APPLICANT FUREKA COUNTY CODE 8.150 REGARDING STATE OF NEVADA

COUNTY COMMISSIONERS APPROVAL

CHARMAN, EUREKA COUNTY CO Alst DAY OF OC:
SHEETS WAS PRESENTED
TOWNSITE. AT A REGULAR MEETING OF THE EUREKA COUNTY COMMISSIONERS HELD ON THE CTOBEK___, 2013, THIS MAP, CONSISTING OF TWO ED AS A PROPOSED PARCEL MAP LOCATED IN THE EUREKA

10-2/43



EUREKA COUNTY HEREBY ACCEPTS THE OFFER OF DEDICATION FOR PUBLIC PURPOSES OF THE PUBLIC UTILITY RIGHTS OF WAY SHOWN ON THIS MAP. THE COUNTY ACCEPTS NO RESPONSIBILITY AND WILL PROVIDE NO SERVICES UPON THE PRIVATE ROAD(S) DESCRIBED, INCLUDING BUT NOT LIMITED TO SNOW REMOVAL.

ACCEPTANCE OF THIS PARCEL MAP BY EUREKA COUNTY DOES NOT CONSTITUTE A GUARANTEE THAT EACH OR ANY LOT SHOWN HEREON CONTAINS A LAWFUL BUILDING SITE. FURTHER REPARCELING OF ANY PARCEL CREATED BY THIS MAP MAY BE SUBJECT TO THE PROVISIONS OF N.R.S. 278.462(3) AND EUREKA COUNTY CODE, TITLE 8, PERMITTING IMPOSITION OF REASONABLE IMPROVEMENT STANDARDS, BUT NOT MORE THAN WOULD BE REQUIRED IF THE SUBSEQUENT PARCEL WERE A SUBDIVISION.

EUREKA COUNTY EXPRESSLY DECLARES THE PRIOR USE OF ADJACENT LAND NEARBY FOR RANCHING, FARMING, AGRICULTURE, MINING, INDUSTRIAL OR COMMERCIAL PURPOSES, AND THE EXPANSION OR MODIFICATION OF SUCH USE, SHALL NOT CONSTITUTE A NUISANCE TO AFTER—ESTABLISHED SUBSEQUENT IN TIME RESIDENTIAL USES PURSUANT TO N.R.S. 40.140 N.R.S. 202.450, AND EUREKA COUNTY CODE 8.120.070. ALL REQUIREMENTS OF GOVERNMENTAL AGENCIES WITH PERMIT AUTHORITY MUST BE MET.

EUREKA COUNTY PLANNING COMMISSION APPROVAL AT A REGULAR MEETING OF THE EUREKA COUNTY PLANNING COMMISSION, EUREKA

COUNTY, STATE OF NEVADA, HELD ON THIS MAP WAS APPROVED. Ħ DAY OF 20/1

CHAIRPERSON (my

10/15/13

RECORDER'S CERTIFICATE

DOC # 0225080

Official Records

Recording requested By
EUREKA COUNTY COMMISSIONERS

Eureka County - NV
Mike Rebaleati - Recorder

Page 1 of 1

Recorded By: FES 225080

APN 001-171-22 PORTION OF PARCEL 1 PM 178257

HUBBARD APN 001-171-22 POR. PARCEL 1 PM 178257

FOUND GLOBRASS CAP

HUBBARD APN 001-171-22 OR. PARCEL 1 PM 178257

N 81.30'50" E 158.

FOUND 5/8" REBAR & CAP PLS 6304

PUE

PUBLIC UTILITY EASEMENT

SANITARY SEWER EASEMENT

MLE

WATERLINE EASEMENT

STORM DRAIN EASEMENT

23****24 {R8}

QUARTER CORNER (COMPUTED

SET 5/8" REBAR WITH CAP PLS 15224

FOUND MONUMENT AS DI

RECORD DATA PER REFERENCE

•

LEGEND

CAP

FOUND & CAP

5/8" REBAR PLS 7998

0

S 89.05'40" W 217.06 (MEASURED TIE)

STREET

PARCEL A [29,295± SF]

PARCEL MAP

FOR

EUREKA COUNTY

A MERGER AND RESUBDIVISION PURSUANT TO NRS 278.4925

LOTS 5-9 OF BLOCK 120 OF THE TOWN OF EUREKA TOGETHER WITH
THE PROPERTY DESCRIBED IN DOC. 171966, BEING LOT 5 OF ROS
BLA FILE NUMBER 171933, EXCEPTING THAT PORTION OF WELL ST
DEDICATED PER RIGHT-OF-WAY DEDICATION FILE NUMBER 171932.

LOCATED WITHIN THE NE1/4 OF SEC 23 & THE NW1/4 OF SEC 24,

TOWNSHIP 19 NORTH, RANGE 53 EAST, MDM

NICHARD

NICHARD

LOCATED PER RIGHT-OF-WAY DEDICATION FILE NUMBER 171932.

TOWNSHIP 19 NORTH, RANGE 53 EAST, MDM

NICHARD

NICH

SHEET

SUMMIT